

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT48584

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2021-22, Date: 01.10.2021

Name of Work:Pothole filling to Roads in Ward No.06 (Thanisandra) Surrounding area Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Chethan P ()	
				In Figures	In Words
1	2563.46	KSRRB- M 3000-2: Making up loss of of Material/irregularities on shoulder of the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per specifications. MORTH Specification No. 3003	Sqm	29.25	Rupees Twenty Nine and Twenty Five Paise Only
2	384.52	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406,	Cum	1939.0	Rupees One Thousand Nine Hundred Thirty Nine Only
3	2564.86	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 compacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification	Sqm	354.0	Rupees Three Hundred Fifty Four Only

Chethan P
Signature of the Contractor

Chethan P
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Shree
3/03